

GUIDELINE FOR GLOVEBOXES THIRD EDITION

AGS-G001

February 2007

**AMERICAN GLOVEBOX SOCIETY
STANDARDS DEVELOPMENT COMMITTEE**

**All Rights Reserved
Copyright 2007**

**No portion may be duplicated without written consent
of the American Glovebox Society.**

ISBN: 1-892643-06-5

Extra copies may be requested as follows:

American Glovebox Society

P.O. Box 9099

Santa Rosa, CA 95405

(800) 530-1022

(707) 578-4406 (Fax)

AGS@gloveboxsociety.org (e-mail)

DISCLAIMER

The American Glovebox Society (AGS) Guideline for Gloveboxes, AGS-G001-2007, has been compiled from established practices and member and contributor experiences. Its intended use is strictly as a guide. Its directions may be altered to suit individual applications. The AGS, its membership, and contributors assume no responsibility for any liability arising out of its use or application.

Table of Contents

1	SCOPE	1
1.1	Limitations	1
1.2	Purpose	1
2	SUPPORTING STANDARDS ORGANIZATIONS	1
3	TERMS AND DEFINITIONS FOR THE PURPOSES OF THIS DOCUMENT	2
4	SAFETY	3
4.1	Design	4
4.2	Fabrication	5
4.3	Installation	5
4.4	Operations	5
4.5	Maintenance	5
4.6	Decontamination and Decommissioning	6
5	DESIGN	6
5.1	Shell	7
5.1.1	Basic Design Considerations	7
5.1.2	Materials	7
5.1.3	Finish	9
5.1.4	Weld Studs and Fasteners	12
5.1.5	Shell Joints	13
5.2	Appurtenances	13
5.2.1	Glove Materials and Systems	13
5.2.2	Transfer Devices	18
5.2.3	Shell Penetrations	30
5.2.4	Fitting	36
5.3	Supports and Stands	37
5.3.1	Safety-Related Supports	37
5.3.2	Industrial Supports	38
5.3.3	Glovebag Supports	38
5.4	Radiation Shielding	38
5.4.1	Requirements	38
5.4.2	Design Considerations	38
5.4.3	Shielding Guidelines	39
5.4.4	Types of Shielding	41
5.4.5	Shielding Windows	42
5.5	Instrumentation and Electrical Considerations	46
5.5.1	Glovebox Pressure	46
5.5.2	Glovebox Filter Pressure Drop	46
5.5.3	Exhaust Duct Airflow	46
5.5.4	Temperature	47
5.5.5	Oxygen Detector	47
5.5.6	Other Atmospheric Monitoring Options	47

5.5.7	Electrical	47
5.6	Atmosphere Systems	48
5.6.1	Glovebox Atmosphere	48
5.6.2	Glovebox Filter Systems	51
5.6.3	Purification Systems	56
5.7	Windows	59
5.7.1	Materials	60
5.7.2	Window Mounting	61
5.8	Fire Protection Systems	64
5.8.1	Glovebox Fire Protection	64
5.9	Interior Equipment	65
5.9.1	Conveyors and Dollies	65
5.9.2	Cranes, Monorails, and Hoists	66
5.9.3	Tanks and Vessels	67
5.9.4	Piping, Tubing, and Valves	69
5.9.5	Blenders, Mills, and Moving Equipment	69
5.9.6	Furnaces	70
5.9.7	Viewing Systems	70
5.9.8	Instruments	70
5.9.9	Manipulators	70
5.10	Human Factors	70
5.10.1	Anthropometry	71
5.10.2	Biomechanical Considerations	71
5.10.3	Gloveports	72
5.10.4	Gloves	72
5.10.5	Illumination	72
5.10.6	Windows	73
5.10.7	Warning Devices—Alarms	73
5.10.8	Controls and Displays	73
5.10.9	Maintainability	74
5.10.10	General	74
5.11	Testing	74
5.11.1	Final Assembly	74
5.11.2	General Criteria for Leak Testing a Glovebox	74
5.11.3	Leak-Testing	75
5.12	Packaging, Loading, Shipping	79
5.13	Decontamination and Decommissioning Design	79
5.13.1	Modular Confinement	79
5.13.2	Liquid Transfer Systems	79
5.13.3	Gaps and Crevices	79
5.13.4	Exhaust Filtration	79
5.13.5	Accumulation of Hazardous Materials	80
5.13.6	Materials Decontamination	80
5.13.7	Equipment Removal	80
5.13.8	Modular Shielding	80
5.13.9	Lifting	80
5.13.10	Pipe Drainage	80

5.14	Mockup and Modeling	80
5.15	Drawing Packages	80
6	FABRICATION	80
6.1	Design for Manufacturability	81
6.1.1	Glovebox Flatness	81
6.1.2	Seal Surface	82
6.1.3	Window Opening Flatness	82
6.1.4	Window Sizing	82
6.1.5	Window Installation Methods	83
6.1.6	Bolted Flange Connections	83
6.1.7	O-Ring Connections	83
6.1.8	Access and Service Panels	84
6.1.9	Gasketing Material	84
6.1.10	Dimensional Tolerances	85
6.1.11	Glovebox Shell	85
6.1.12	Measurement Techniques	87
6.2	Welding	87
6.2.1	Capacitive Discharge Stud Welding	87
6.2.2	Gas Metal Arc Welding (GMAW)	88
6.2.3	Gas Tungsten Arc Welding (GTAW)	88
6.2.4	Plasma Arc Welding (PAW)	89
6.2.5	Routine Weld Repair	89
6.2.6	Glovebag Seam Heat Sealing	89
6.3	Cutting and Forming	89
6.3.1	Shearing	89
6.3.2	Plasma Arc Cutting	89
6.3.3	Saw Cutting	90
6.3.4	Laser Cutting	90
6.3.5	Water Jet Cutting	90
6.3.6	Forming Dies and Cold Forming Operations	90
6.3.7	Punching and Notching	90
6.3.8	Nibbling	91
6.3.9	Abrasive Disc Cutting	91
6.4	Assembly	91
6.5	Weld Inspection	91
6.5.1	Visual Examination	91
6.5.2	Dye Penetrant Examination	91
6.5.3	Radiography	92
6.5.4	Ultrasonic and Eddy Current	92
6.6	Personnel Qualifications	92
6.6.1	Welders	92
6.6.2	Inspectors	92
6.6.3	Finishers	92
6.6.4	Layout	93
6.7	Finishing Requirements	93
6.8	Cleaning Methods	93

6.8.1	General.....	93
6.8.2	Mechanical.....	94
6.8.3	Chemical.....	94
6.9	Shipping.....	95
6.9.1	Shipping Approval.....	95
6.9.2	Final Cleaning.....	95
6.9.3	Packing.....	95
6.9.4	Package Labeling.....	95
6.9.5	Lifting.....	95
6.9.6	Shipping.....	95
6.9.7	Glovebag Packaging.....	96
6.10	Glovebox Permanent Identification Labeling.....	96
7	LININGS.....	98
8	INSTALLATION.....	98
8.1	Isolation from Surrounding Activities.....	98
8.2	Site Preparation.....	98
8.3	Receiving and Unpackaging.....	98
8.4	Penetrations.....	99
8.5	Connection of Existing Building Services and Appurtenances.....	99
8.6	Ventilation Installation.....	99
8.7	Installation of Interim Equipment.....	99
8.7.1	General.....	99
8.7.2	Preparation and Installation of Glovebags.....	99
8.8	Fire Protection Systems.....	100
8.9	Inspections to Ensure Integrity and Quality Installation Qualification.....	100
8.10	Damage Repair.....	100
8.11	Leak Tests.....	100
8.11.1	Introduction.....	100
8.11.2	Glovebox Preparation.....	101
8.11.3	System Test.....	101
8.11.4	Differential Pressure Leak Test Method.....	101
8.11.5	Mass Spectrometer Leak Detector Testing.....	101
8.12	Containment Integrity Testing and Ventilation Flow Characterization.....	102
8.12.1	Introduction.....	102
8.12.2	Preparation.....	102
8.12.3	Material Transfer Integrity Test.....	102
8.12.4	Glove Changeout Integrity Test.....	103
8.12.5	Ventilation Flow Characterization Test.....	103
8.12.6	Post-Test Cleanup.....	103
9	OPERATIONS.....	103
9.1	Gloveports.....	103
9.2	Gloves.....	104
9.3	Glove Changes.....	104

9.4	Glovebox Monitoring.....	105
9.4.1	Airflow Monitoring.....	105
9.4.2	Differential Pressure.....	105
9.4.3	Glovebox Flow Rate.....	105
9.4.4	Oxygen Concentration.....	105
9.4.5	Operator Awareness.....	105
9.5	Cleaning.....	105
9.6	Periodic Inspections or Certifications.....	105
9.6.1	Glove Inspection.....	105
9.6.2	Leak Detection.....	105
9.6.3	Surveillance Documentation.....	106
9.7	Control of Test Equipment.....	106
9.8	Training for Operator Qualification.....	106
9.8.1	Training Program Structure.....	106
9.8.2	Qualifications.....	110
9.8.3	Review and Audit.....	110
10	MAINTENANCE AND RECORDS.....	110
10.1	Procedures.....	110
10.1.1	General Equipment Removals.....	110
10.1.2	Replacement of Windows and Window Gaskets.....	110
10.1.3	Glove Change-out.....	111
10.1.4	Non-window Gasket Change-out.....	111
10.1.5	Filter Replacement.....	112
10.2	Glove Change Program.....	113
10.2.1	Statistical Methodology.....	113
10.2.2	Environmental Factors.....	113
10.3	Labeling and Documentation.....	113
10.3.1	Component Labeling.....	113
10.3.2	Documentation.....	114
10.4	Training for Maintenance Personnel.....	114
11	DECONTAMINATION AND DECOMMISSIONING GLOVEBOX FACILITIES.....	114
11.1	Safety.....	115
11.1.1	Work Environment.....	115
11.1.2	Planning and Procedures.....	115
11.1.3	Temporary Contamination Control.....	115
11.1.4	Gloves, Coveralls, Pads.....	115
11.1.5	Dosimetry.....	115
11.1.6	Prejob Survey.....	115
11.2	Glovebox Preparation.....	115
11.2.1	General.....	115
11.2.2	Equipment Removal.....	115
11.2.3	Isolation.....	115
11.2.4	Waste Categorization.....	115
11.2.5	Disposal Containers.....	115

11.2.6	Ongoing Work	115
11.2.7	Additional Containment	116
11.2.8	Removable Panels.....	116
11.2.9	Piping	116
11.2.10	Final Removal.....	116
11.2.11	Decontamination.....	116
11.3	Glovebox Removal.....	117
11.3.1	General.....	117
11.3.2	Contamination Enclosure.....	117
11.3.3	Monitoring	117
11.3.4	Coatings	117
11.3.5	Internal Openings.....	117
11.3.6	Packaging.....	117
11.3.7	Internal Fixtures and Equipment	117
11.3.8	Glovebox Removal	118
11.3.9	Clean The Work Area.....	118
11.3.10	Dispose of Waste	118
11.3.11	Remove Contamination Enclosure	118
12	QUALITY ASSURANCE	118
12.1	Management Responsibility.....	119
12.2	Quality System	119
12.3	Contract Review.....	119
12.4	Design Control	120
12.5	Document and Data Control.....	120
12.6	Purchasing.....	120
12.6.1	General	120
12.6.2	Suspect/Counterfeit Products.....	121
12.7	Control of Customer-Supplied Material.....	122
12.8	Product Identification and Traceability.....	122
12.9	Process Control and Continual Improvement.....	122
12.10	Inspection and Testing	123
12.11	Control of Inspection, Measuring, and Test Equipment.....	124
12.12	Inspection and Test Status.....	124
12.13	Control of Nonconforming Product	124
12.14	Corrective and Preventative Action and Product Improvement.....	124
12.15	Handling, Storage, Packaging, Preservation, and Delivery.....	125
12.16	Control of Quality Records	125
12.17	Quality Audits.....	125
12.18	Training.....	125
12.19	Servicing	125
12.20	Statistical Techniques.....	126
12.21	Applicable Standards	126

13 REFERENCES	128
APPENDIX A—DRAWINGS	133
APPENDIX B—EXAMPLE OF A VENDOR EVALUATION PROGRAM	159
B.1 Purpose.....	159
B.2 Scope.....	159
B.3 References.....	159
B.4 Definitions (specific to Appendix B).....	159
B.5 Responsibilities.....	160
B.6 Suggested Procedure.....	160
B.7 Evaluator Qualifications.....	163
APPENDIX C—AGS-G001-2006 GLOVEBOX DESIGN CHECKLIST	C-1
APPENDIX D—AGS-G001-2006 GLOVEBOX COMMISSIONING CHECKLIST	D-1
INDEX	175

List of Figures

FIGURE 5.1. Standing seam joint.	13
FIGURE 5.2. Glovebox Glove Dimensions	16
FIGURE 5.3. Glovesleeve installation.....	19
FIGURE 5.4. Glovebag operation.	19
FIGURE 5.5. Bagport ring assembly.....	20
FIGURE 5.6. Inner bagport ring assembly.....	21
FIGURE 5.7 Bagport cover assembly.	21
FIGURE 5.8. Transfer sleeve configuration.....	23
FIGURE 5.9. Bagport ring assembly.....	23
FIGURE 5.11 Removal materials from a continuous flow airlock.	27
FIGURE 5.12 Sphincter seal assembly.....	29
FIGURE 5.13. Principle of double-door transfer system.	30
FIGURE 5.14. Double-door waste drum system.....	32
FIGURE 5.15. Typical bulkhead union with swaged ferrules.....	33
FIGURE 5.17. CGB bulkhead feedthrough.....	35
FIGURE 5.18. High-integrity push-through. connector.....	36
FIGURE 5.19. Service fitting with an O-ring seal.....	36
FIGURE 5.20. Typical shielding sandwich.....	41
FIGURE 5.21. Typical shielding window.	43
FIGURE 5.22. Inert atmosphere Control System.....	50
FIGURE 5.23. Glovebox air purification system.	57
FIGURE 5.25. Zipper window assembly.....	61
FIGURE 5.26. Clamped window assembly.....	63
FIGURE 5.27. Window bolt torquing sequence.....	64
FIGURE 6.1 Sample nameplate.....	97
FIGURE 9.1 Data sheet for leak rate test	107
FIGURE 9.2 Glovebox - leak rate calculations	108
FIGURE 10.1 Sample glovebox component labels.....	114